Quality control procedure.

Checks from start to handover

VERSION	APPROVED	OWNER	WEB
1.0	27 October 2026	Managing director	pblondal.is/en/policies/gaedaeftirlit/

Quality control means systematically checking the things that matter before mistakes are covered up or work is handed over. P. Blöndal ehf. runs simple but reliable checks linked to the actual stages of the work, particularly excavation, soil replacement, pipe beds, fill, compaction and surface finishing. The amount of documentation depends on the risk, the contract and the client's requirements.

Preparation and documents

Before work begins, the latest approved drawings, material specifications, reference levels, quantities and agreed boundaries of the work must be in place. Any mismatch between the drawings and actual conditions is clarified before the wrong work is carried out. The scope of subcontractors and responsibility for surveying, testing and handover must be clear.

Checks during the work

Before work is covered, such as a pipe bed or fill, the base and the properties required by the contract are confirmed. In pipe work, attention is paid to position, depth, protective layers and the surveying the pipe owner requires. In paving, the sub-base, compaction, falls and edging are what matter. Where measurement or testing is needed, it is carried out by a competent party using an approved method before anything is covered.

Deviations and change management

When deviations are found, they are defined, the client is informed and an approved solution is sought before the change becomes irreversible. Deviations in quantities, materials or design are not concealed. For extra work, the scope, price and effect on the schedule are confirmed as far as possible before the work begins. Evidence may include photos, measurements, correspondence or other relevant documents.

Handover

At completion, surfaces, clean-up, access, drainage, repairs to disturbed areas and any items the client has requested are reviewed. The final handover separates completed work from outstanding items and makes clear who is responsible for any corrections. This way, disagreements about scope and quality are more likely to be resolved on the basis of records.

Responsibility and review

The managing director is responsible for this document and for making sure its content is presented to everyone working on the company's behalf. It is reviewed when there are significant changes to the work, equipment or rules, after incidents, and otherwise regularly in line with the scale of the business.